QUAILE ENGINEERING LTD.



38 Parkside Drive UNIT 7 Newmarket, ON L3Y 8J9 Tel: (905) 853-8547 Toll Free: 1-877-364-5209 Email: quaile.eng@rogers.com

May 13, 2019

Mr. Mark Paisley Southgate Manufacturing Inc. 6393 Yatton Sideroad Wallenstein, Ontario NOB 2SO

Re: Thickness testing of veneer ties

Dear Mark:

This is to confirm that we received a number of 7/8" x 6.6" long veneer ties for thickness testing. We used a micrometer to measure the thickness of five separate ties to the nearest 0.001" (0.025 mm).

We found the thickness to range from 0.031" to 0.036" (0.787 mm to 0.914 mm). This meets Ontario Building Code 9.20.9.5 (b) requirement for a minimum 0.76 mm thickness.

Yours truly,

Stephen Boyd, P.Eng.

Staple loyd

C:\Users\Steve\Documents\SJB-3\Drawings\2019\19-109 Veneer Tie\19-109 Southgate Veneer Tie - May 13-19.docx